

VTA's BART Silicon Valley Phase II Extension Project

October 28th Street/Little Portugal
Community Working Group Meeting

October 8, 2025

28th Street/Little Portugal CWG Members



- Bill Rankin, *Friends of Five Wounds Trail*
- Chris Patterson-Simmons, *East Village San Jose*
- Danny Garza, *Plata-Arroyo Neighborhood Association*
- **Davide Vieira**, *Five Wounds Portuguese National Parish*
- Dee Barragan, *Roosevelt Park Neighborhood Association*
- Elma Arredondo, *Alum Rock Urban Village Advocates (ARUVA)*
- Elsa Oliveira, *Portuguese Organization for Social Services & Opportunities (POSSO)*
- Ed Berger, *Northside Neighborhood Association*
- Helen Masamori, *Five Wounds/Brookwood Terrace Neighborhood Action Coalition; Alum Rock Santa Clara Street Business Association*
- Damone Jordan, *Cristo Rey San Jose Jesuit High School*
- Jesus Flores, *Five Wounds Latino Business Foundation*
- Justin Triano, *Ride East Side San José (Ride ESSJ)*
- Melissa Canela, *School of Arts and Culture at the Mexican Heritage Plaza*
- Terry Christensen, *CommUniverCity*
- Tala Fatolahzadeh, *City of San José*
- Eric Eidlin, *City of San José*
- Chris Burton, *City of San José*
- Scott Smith, *BART*

AGENDA

- I. 28th Street/Little Portugal Design Development Framework (DDF)
- II. Peer Review Report Out
- III. Cost Savings Status
- IV. Construction Updates
- V. Path Forward & Next Steps



28th Street/Little Portugal Design Development Framework

PROJECT UPDATE: VTA's 28th St/Little Portugal Design Development Framework (DDF)

SEASON 3 OF ENGAGEMENT – *Thank you for participating!*

Public Comment Period August 14 to September 18

- DDF Public Meeting
- Viva CalleSJ + La Plaza's Chile, Mole, Pozole Festival
- SJ High Portuguese Class + Cristo Rey SJ Info Session
- SJ Youth Commission
- ...and more

NEXT STEPS:

- **November:** VTA Advisory and Standing Committees
- **December:** VTA Board Meeting



vta.org/28LPdevelopment

EXECUTIVE SUMMARY	4
1 INTRODUCTION	6
1.1 Organization	7
1.2 Terms and Definitions	7
1.3 References	8
1.3.1 VTA Policies	
1.3.2 City Policies and Development Standards	
1.3.3 Additional Guidance	
2 VISION	10
2.1 Concept Visioning	14
3 CULTURE AND COMMUNITY	16
3.1 Art and Culture	22
3.1.1 Art and Heritage	
3.1.2 Process and Partnerships	
3.2 Open Space	26
3.2.1 Character	
3.2.2 Landscape Features	
3.2.3 Station Plaza	
3.2.4 Neighborhood Park	
3.2.5 Gateway Park	
3.2.6 Paseos	
3.3 Active Uses	38
3.3.1 Use Types	
3.3.2 Ground Floor Activation	
3.3.3 Phasing and Interim Use	
4 URBAN FABRIC AND ENVIRONMENT	44
4.1 Block Structure	48
4.2 Land Use	50
4.3 Buildings	52
4.3.1 Height	
4.3.2 Massing and Orientation	
4.3.3 Character	
4.3.4 Ground Floor Design	
5 MOBILITY AND CONNECTIVITY	64
5.1 Active Mobility Network	68
5.1.1 Streetscape Design	
5.1.2 Five Wounds Trail/N. 28th Street	
5.1.3 Sightlines, Wayfinding, and Signage	
5.2 Transit Network	79
5.3 Vehicular Network	80
5.3.1 Vehicular Access	
5.3.2 Curb Management	
5.3.3 Off-Street Loading and Parking	
6 GLOSSARY	86

DDF Community Engagement: 3 Seasons

Participación comunitaria del DDF



~ 1,000+ Total touchpoints across:
puntos de contacto a travez de:

- Stakeholder meetings
- Youth engagement
- Pop-ups at events
- Juntas con partes interesadas
- Enganche juvenil
- Eventos estilo "pop-up"




Photos from Season 3 of Engagement

Peer Review Final Report Out



- **Independent perspective** on Value Engineering efforts to bring the scope and budget into alignment.
- **Feedback** on the feasibility, constructability, packaging, and delivery to reduce costs and match available funding.
- **Enable VTA to move forward** with a project configuration for a forthcoming FFGA.

- First day of two-session Peer Review held on August 20
- Panel included project delivery executives from peer transit agencies:
 - Sound Transit – Seattle, WA
 - LA Metro – Los Angeles, CA
- Attendees included VTA Project Team, FTA, PMOC, BART, and Gall Zeidler



- Presentation by staff on project background, baseline, and two scenarios (incorporating cost savings)
- Tour of project alignment and west portal construction site
- Focus on **feasibility**, **constructability**, **contract packaging** and **delivery methods**





- Evaluation of Scenarios
 - **Scenario 1 is optimal path forward** from a constructability and feasibility perspective, offers fewer risks
 - **Scenario 1a introduces additional costs**, a cut-and-cover box in downtown San Jose, impact to community, increase risk and complexity
- Cost Estimates and Risk Adjustments
 - Recommends cost estimates be updated to reflect **evolving market conditions**
- Contract Packaging
 - Breaking up large contracts into **smaller packages** will improve bidder interest and **reduce integration risk**—if managed effectively
 - Repackaged tunnel contract must include clear provisions for **system integration** and **TBM-related risk mitigation**

- VTA/BART Partnership
 - A **strong working relationship between VTA and BART** is critical to the success of the project.
 - Encourages VTA and BART to continue efforts to **maintain this relationship** given the challenges of such a long and complex project
- Newhall Yard Refinements
 - **Achieving concurrence** between BART and VTA on Newhall Yard refinements needs to be a priority for the project to proceed successfully
- **Continue the Project momentum** with early construction underway



Cost Savings Status



- **Outstanding Cost Savings items under consideration:**
 - Systems
 - Downtown station design
 - Newhall Yard
 - Project Configuration (Scenarios 1 or 1a)
- **Continued Stakeholder Engagement** re: Downtown San Jose station refinement
- **Planning Future Engagement with BART** re: Newhall Yard

Scenario 1 Refinements at Stations




- Relocated **station infrastructure facilities (SIF) above ground** and optimized station equipment layout
- Implemented **systems efficiencies** to reduce SIF footprint
- Modified deep shaft and adit configurations (***not affecting passenger experience***)
- Optimized station entrance architectural layout and footprints
- Consolidated and **removed egress shaft at Diridon**
- Use of cost-effective materials
- Converted parking garages to **surface parking** (28th Street/Little Portugal and Santa Clara stations)

Engagement on Station Infrastructure Facility in Plaza



- Features & finishes (screening, architectural, artwork)

To be discussed with CWG:
28th/Little Portugal: Q1/Q2 2026
DTSJ: Q3/Q4 2026
Diridon: Q1/Q2 2026
Santa Clara: Q3/Q4 2026



Engagement on Station Infrastructure Facility in Plaza



- Landscaping & hardscaping around Station Infrastructure Facility

To be discussed with CWG:
28th/Little Portugal: Q1/Q2 2026
DTSJ: Q3/Q4 2026
Diridon: Q1/Q2 2026
Santa Clara: Q3/Q4 2026




Downtown Berkeley BART Station Plaza Vent Structure

Why Does Project Configuration Matter?




- Scenario 1 vs. Scenario 1a Configuration
- Configuration Dictates:
 - How project advances to 60% design
 - Approach to critical path tunnel construction
 - Ability to stay on schedule and meet projected revenue service date
 - Flexibility to proceed if FFGA is delayed
- How to choose:
 - Advice from independent Peer Review (risk, schedule, industry readiness)
 - Project team cost and schedule estimates
 - Feedback from Gall Zeidler

Configuration: Scenario 1 & 1a



Scenario 1

Scenario 1a – Concurrent Tunneling





Additional Construction Considerations:

- Smaller single bore for portion of alignment
- New East Portal launch structure & Additional TBM
- 28th Street/Little Portugal station: large cut-and-cover box structure
- Retrieval shaft at “meet up” location of two TBMs


Schedule Considerations:

- Initial start-up activities to launch TBM from East Portal
- Faster tunneling rate for smaller TBM
- Extraction of two TBMs

Smaller Tunnel Diameter Analysis




Smaller Single-Bore Tunnel



~40' TBM
Diameter

One 22' Wide Center Platform
Cannot Fit Within Tunnel

Larger Single-Bore Tunnel



~53' TBM
Diameter

22' Wide Center Platform

Conceptual layout

Scenario 1a:


New East Portal Launch Structure & Additional TBM




Overview:

- Design, procurement, and fabrication of an additional 40' TBM
- East Portal becomes a Launch Shaft rather than a reception shaft
- Changes to East Portal:
 - Larger temporary excavation for assembly and launching the TBM.
 - Increased temporary power for TBM
 - Larger staging area (additional ROW)
 - More tunnel spoil off-haul traffic
 - Site would have similar operations as the West Portal Launch Structure and surrounding site


Environmentally Cleared East Portal Construction Staging Area and Tunnel Launch Structure



Scenario 1a: Cut & Cover at 28th Street/Little Portugal Station



Smaller Tunnel: Fully Cut-and- Cover Station



Legend


-  Station Headhouse & Station Infrastructure Excavation
-  Tunnel Shaft
-  Extent of Open Cut-and-Cover Excavation

Scenario 1a: Meet-up Location




Overview:


- The two TBMs would meet in Downtown San Jose at one block between 3rd Street and 7th Street
- Addition of “meet-up” shaft
- Anticipated construction activities:
 - Early Works demo, utility relocation, instrumentation and well installation
 - Slurry wall construction
 - Excavation and road decking
 - Crane mobilization/demobilization, and TBM dis-assembly and off-haul for the two TBMs
 - Shaft backfill and road reinstatement




Example Configuration of Meet Up Shaft



Concurrent Tunneling Schedule (Scenario 1a)



Scenario 1 Configuration



Downtown Construction Update

Downtown Building Demolition & Clean Up



Location: 22-55 N. First Street

Duration: As early as November 2025 to January 2026; Monday-Friday 7AM-4PM


What to Expect:

- No impact to public roads, VTA bus and light rail service.
- Sidewalk closure in front of building during demolition (~1 month)
- Access to VTA public parking lot will be available throughout duration of work, with limited parking available.
- Minor to moderate noise and vibration during demolition.
- Minor noise during off haul activities.




West Portal Construction Update

West Portal Construction Area




DRAFT as of 10/8/2025 – FOR DISCUSSION ONLY


Where is the West Portal and TBM Launch Structure



Tunnel Launch Structure



Y-Panels Overview



CATERPILLAR SHAFT PLAN - PANEL BITE LAYOUT

- Main structural element of Caterpillar Shaft
- Number of Y-Panels = 8
- Panel Depth = 133.5 ft
- Total Volume of Concrete = **5,929 cu yd**
(approx. **658 concrete trucks**)


Y-Panel Rebar Cage Crane



- Crane Model: **Liebherr LR 11000 S2** Crawler Crane
- Track Dimensions = **40'-10"** Long x **8'-3"** Tall, **7'-10"** Wide
- Configuration = Main Boom **S2**
- Boom Length = **217 ft**
- Counterweight = **551.25 kip (275 tons)**
- Car Body Counterweight = **198.45 kip (99.25 tons)**
- Max Capacity of Crane with 217 ft Boom Length = **944 kip (472 tons)**
- 1 US ton = 2 kip



Boom length limited
to 217ft



West Portal Construction Progress



The above “tripping frame” has been designed specifically to manage the lifting of the Y-Panel cages (weighing over 300,000lbs) to the vertical position





Test lift of “tripping frame”

Y-Panel Tripping & Lifting Sequence





- Phase 1 - Initial Pick:
 - Rebar cage assembled inside tripping frame
 - Lifting frame connected to rebar cage.
 - Lifting frame connected to tripping frame.
 - Crane rigged to lifting frame.



Y-Panel Tripping & Lifting Sequence




- Phase 2 through 9 – Pivot and Tripping Actions:
 - Structure is lifted from horizontal to vertical rotating about the pivot frame
 - Crane lifts and tracks the frame throughout this phase
 - Structure is tripped over the pivot frame.
 - Tripping action provides a controlled and safe handling of the frame.



Y-Panel Tripping & Lifting Sequence



- Phase 10 - 11 Lifting the Rebar Cage and Rebar Cage Transport:
 - Tripping frame secured to the pivot frame.
 - Lifting frame disconnected from tripping frame.
 - Lifting frame remains connected to rebar cage.
 - Rebar cage strapping removed.
 - Lifting frame connected to rebar cage.
 - Rebar cage transported to Y-Panel location



DRAFT as

PHASE 10 - SECTION
11



Tripping Frame



DRAFT as of 10/8/2025 – FOR DISCUSSION ONLY



Rebar Cage Lift – Support Walls

West Portal Construction Progress



Excavation of launch structure, placement of struts and walers


West Portal Construction Progress



Multiple concrete trucks for Y-Panel 12 hour pour



Pressure washing Y-Panel




Preparing rebar for next “trip” and lift

Tunnel Boring Machine



Tunnel Boring Machine




Tunnel Boring Machine




Path Forward & Next Steps


Path to FTA Full Funding Grant Agreement (FFGA)




Path to FTA Full Funding Grant Agreement (FFGA)



Critical Activities to Tunnel Construction



Contract Packaging & Delivery Methods Next Steps



Recent Engagement Activities

- Ongoing coordination with Cities
- Downtown San José Station Design Engagement (x7)
 - SJ Downtown Association Briefing
 - SJ Chamber of Commerce Briefing
- Construction Noticing for PG&E Road Closure for Gas Utility Work
- 9/23 Interim Downtown-Diridon Community Working Group Meeting
- Stakeholder Engagement:
 - Cristo Rey San Jose Jesuit High School Freshmen Parent Night
 - Reimagining Santa Clara Street Study (CSJ-led study)
 - San Jose Arena Authority Board
- 10/4 Santa Clara Parade of Champions
- 10/7 City of Santa Clara Council Meeting
- 10/7-10/9 Community Working Group Meetings

Upcoming Engagement Activities

- Ongoing Stakeholder Briefings
- Cristo Rey San José Jesuit High School
- Construction Media Tour



*VTA Strategic
Plan Open
House*



- Continued Stakeholder Engagement re: Downtown San Jose station refinement
- Planning Future Engagement with BART re: Newhall Yard
- October 9 BSVII Oversight Committee Meeting
- October 10 VTA/BART Joint Working Committee
- October 17 Board Workshop/Special Meeting
 - Path Forward (Cost Saving Scenario, FFGA timeline, Contract Packaging Update)

Questions?